




RECEIVED  
3/25/2026

COMMONWEALTH OF PENNSYLVANIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
BUREAU OF OIL AND GAS MANAGEMENT

DEP USE ONLY	
Auth # 1564247	APS # 1159558
Site # 887154	Facility # 891111
Client # 27639	Sub-facility # 1473319

**APPLICATION FOR AN ORDER TO CLEAN OUT AND PLUG OR REPLUG  
A NON-PRODUCING GAS WELL UNDER SECTION 13(C) of ACT 214**


Please read instructions on reverse before completing this form

SECTION A. APPLICANT INFORMATION	SECTION B. OTHER AFFECTED PARTIES
Name Equitrans, LP	<b>SURFACE OWNER</b>
Address 2200 Energy Drive	Name John R. & Loise M. Hildreth
City Canonsburg State PA Zip 15317	Address 541 Patterson Creek Road
Telephone 412-584-3132 Fax	Address Sycamore, PA 15364
<b>GAS WELL INFORMATION</b>	<b>OIL AND GAS LESSOR</b>
Farm Name 7371	Name John R. & Loise M. Hildreth
Well No. 7371 Serial No.	Address 541 Patterson Creek Road
Municipality (City, Borough, or Township) Morris Township	Address Sycamore, PA 15364
County Greene	Phone Fax
Well Permit/Reg. No., if known TBD 059-28671 Date Drilled, if known	<b>OIL AND GAS LESSEE</b>
Is this well the object of a Coal Pillar Permit? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Name Equitrans, LP
<b>SECTION C. ADDITIONAL INFORMATION REQUIRED</b>	Address 2200 Energy Drive
<b>Checklist</b>	Address Canonsburg, PA 15317
Well Location Plat: Form 5500-FM-OG0002 <input checked="" type="checkbox"/>	Telephone 412-584-3132 Fax
Copy of or record reference to a deed, lease or other document entitling the applicant to enter upon the surface land <input checked="" type="checkbox"/>	<b>SECTION D. SIGNATURE BLOCK</b>
Proposed method of cleaning out, plugging or replugging the well <input checked="" type="checkbox"/>	I HEREBY CERTIFY THAT I HAVE SENT BY Certified or Registered Mail a copy of this application to the surface landowner, the oil and gas lessor and lessee as identified above, and the coal owners and operators of all mineable coal seams.
Notice of Intention to Plug (5500-FM-OG0005) (If previously submitted check this box) <input type="checkbox"/>	
If alternative method of plugging is proposed, is Form 5500-PM-OG0024 attached? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Signature of Applicant
	Megan Stahl - Land Officer 3/18/2026
	Type or Print Name and Title Date

Objection Date: 04/24/26

Email: jazavatchan@eqt.com

Reviewed by  
HLC 4/27/2026



 04/27/26



COMMONWEALTH OF PENNSYLVANIA  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 OFFICE OF OIL AND GAS MANAGEMENT  
**WELL LOCATION PLAT**  
 PAGE 1 Surface Location

DEP USE ONLY	Auth ID#:	G:
	Permit #:	04/27/26
	Project #:	C:


SHL TRUE LATITUDE:
<b>39.937107</b>
SHL TRUE LONGITUDE:
<b>-80.333764</b>



**LEGEND**

- 7371
- ACTIVE GAS WELL
- WATER SOURCE
- LINE TYPES
- BLUE LINE STREAM OR POND
- WETLAND
- PROPERTY LINE
- TIE LINE
- BUILDING/STRUCTURE
- HARVEY MINE
- SWARTS STORAGE BUFFER

NOTE: It is not the purpose or intention of this plat to represent surveyed locations of the surface or mineral parcels depicted herein. The location of the boundary lines, as shown are based on recorded deed descriptions, field evidence found, aerial mapping and/or tax map position, unless otherwise noted.



Applicant / Well Operator Name: EQUITRANS L.P.		DEP ID #: OGO-36770 36670	Well (Farm) Name: 7371		Well #:	Serial #:
Address: 2200 ENERGY DRIVE, CANONSBURG PA 15317			County: GREENE	Municipality: MORRIS TOWNSHIP	Well Type: GAS	
911 Address of Well Site: N/A			USGS 7.5' Quadrangle Map Name: ROGERSVILLE	Map Section: 4	Surface Elevation: 1065'	
Surveyor: Boord, Benchek and Assoc. BRIAN DOUGLAS SOKOL SURVEYOR No. SU075636		Phone #: 724-746-1055	Dwg #: 4097	Date: MARCH 17, 2026	Scale: 1" = 400'	Tract Acreage: 208.17 +/-
Lat. & Long. Metadata Method: GPSKN	Accuracy: 4'	Datum: NAD 83	Elevation Metadata Method: GPSKN	Accuracy: 6'	Datum: NAVD 88	Survey Date: SEPTEMBER 18, 2024



7371  
Greene County, PA  
Swarts Field  
API # Unknown  
By: EQT Production  
Date: 9/30/2024

**Current Status:**

**Casing/tubing information not available due to lack of known Well Record**

**3<sup>rd</sup> String** casing @ N/A, cement N/A  
**2<sup>nd</sup> String** casing @ N/A, cement and packer N/A  
**1<sup>st</sup> String** casing @ N/A  
TD: Unknown

Elevation: N/A  
Water @ N/A  
Coal @ N/A  
Oil @ N/A  
Gas @ N/A

**\*Cement plugs will be cemented with Class A or Class L cement**

1. Notify State Oil and Gas Inspector 48 hours in advance of commencement of plugging operations.
2. **Conduct Tailgate Safety Meeting. Complete JSA's as required.**
3. Check Vent for gas, if clear dig sump around monument.
4. MIRU Conductor rig.
5. Drill in as much conductor as possible and cement annulus of conductor.
6. RDMO with Conductor rig
7. MIRU Plugging rig. Begin plugging and abandonment operations.
8. Ensure containment is secure around well head.
9. Clean out well to 405' and run pressure protective casing. Cement to surface on annulus of protective casing.
10. Rig up BOPs
11. Continue to clean out to TD or PADEP approved attainable bottom.
12. RIH w/wireline and run CBL on **1<sup>st</sup> String** casing from **1<sup>st</sup> String Casing Shoe Depth** to surface to determine bonded casing.
13. Contact EQT REP and DEP Inspector with Bond Log results and determine perforating and cutting schedule.
14. Attempt to pull **1<sup>st</sup> String** casing per DEP regulations of 120% or 5K which is ever greater.
15. Perforate **1<sup>st</sup> String** casing where specified.
16. TIH w/ tubing and cement from TD or PADEP approved attainable bottom to surface.
17. Top off well to surface with solid cement as needed.
18. Install casing vent and above grade monument at least 5' with API#, company information and date plugged. Mark GPS of well for future inspections.
19. Rig Down, move off.
20. Restore well site and access road according to PA DEP regulations.

## SURFACE INDEMNITY AGREEMENT

This Surface Indemnity Agreement (“Agreement”) is entered into this 3<sup>rd</sup> day of July, 2025 by and between John R. Hildreth and Louise M. Hildreth, H/W, whose mailing address is 541 Patterson Creek Road, Sycamore, PA 15364 (“Owner”), and EQT Production Company, a Pennsylvania corporation, with an office located at 625 Liberty Avenue, Suite 1700, Pittsburgh, PA 15222 (“EQT”). Owner and EQT are individually referred to hereinafter as a “Party” and collectively as the “Parties”.

WHEREAS, Owner is the owner of the surface of certain real property located in Morris Township, Greene County, Pennsylvania, identified as Tax Map Number 18-05-0130, and being the same tract or parcel of land conveyed to Owner in Deed Book 364, Page 1192, (the “Property”); and

WHEREAS, EQT is (1) the current working interest owner in that certain oil and gas lease recorded in the Office of the Recorder of Deeds of Greene County, Pennsylvania pertaining to the Property (the “Lease”); and (2) the owner of that certain oil and gas well(s) located on the Property and more particularly described as “R G Rutan 1001, 7371, A223”, API No. 3705928361, L-028842, L-028843 (the “Well”); and

WHEREAS, Owner purchased the Property with the existing Well located on the surface; and

WHEREAS, EQT intends to enter onto the Property pursuant to the rights and privileges set forth in the Lease in order to commence plugging operations (“Plugging Operations”) on the Well, and the Parties desire to memorialize their understanding with respect to same.

NOW THEREFORE, for the good and valuable consideration as set forth herein, Owner and EQT, intending to be legally bound, agree as follows:

1. Acknowledgment of Rights. Owner hereby acknowledges EQT’s right of entry upon the Property in order to conduct Plugging Operations pursuant to EQT’s rights and privileges granted in the Lease, and Owner shall not interfere with EQT’s exercise of such right.
2. Industry Best Practice and Compliance with Law. In its performance of the Plugging Operations, EQT shall use industry best practices and shall comply with and adhere to all applicable laws and regulations.
3. No Modification. It is expressly understood and agreed that EQT’s rights, title, and interest in and to the Property and other land, and oil and gas located thereon and thereunder, under law or any agreement, including but not limited to the Lease, are not abridged, terminated, limited, restricted, altered, or otherwise modified by this Agreement.
4. Indemnification. EQT shall indemnify, and defend and hold Owner harmless from any and all liabilities, liens, demands, judgments, suit(s), and claim(s) of any kind or charter arising out of, in connection with, or relating to EQT’s operations under the terms of this Agreement, including, but not limited to, environmental issues, claim(s) for injury to or death of any person, or damage, loss or destruction of any property, real or personal, under any theory of tort, contract, or strict liability (“Claims”). Owner, if it so elects, shall have the right to participate, at its sole expense, in its defense in any suit in which it may be a party, without relieving EQT of the obligation to defend Owner. Notwithstanding the foregoing, EQT shall not be obligated to indemnify or defend Owner against any Claims that are caused, impacted, or influenced by the actions, omissions, negligence, gross negligence, or misconduct of Owner, Owner’s successors, assigns, contractors, subcontractors, representatives, agents, or any third party.


5. Miscellaneous. This Agreement shall benefit and be binding upon EQT and Owner and their successors and assigns. This Agreement shall be governed by and construed in accordance with the laws of Pennsylvania. The terms of this Agreement shall be confidential and Owner shall not disclose the same to any other person or entity without prior written consent of EQT, except as required by law or court order. The Parties have had opportunity to seek advice of legal counsel in the negotiation of this Agreement, and this Agreement shall not be construed in favor of or against any Party. If any of the provisions of this Agreement are held by a court to be invalid, void or otherwise unenforceable, the remaining provisions shall remain enforceable. Owner shall not object to ordinary permit filings or applications made by EQT in connection with the Purpose or any related improvements or facilities, nor interfere with the activities of EQT or its contractors or agents on the Property. This Agreement may be executed in multiple counterparts, each of which will be deemed to be an original, and collectively shall be deemed one single agreement.
6. EQT agrees to repair and reclaim any future slips occurring within the Limits of Disturbance ("Slip Repair Site") that are directly and solely related to EQT's Plugging Operations on the Property, for a period of three (3) years following completion of reclamation of the site on the Property. Landowner hereby grants unto EQT the rights necessary and convenient to repair and reclaim the Slip Repair Site, including ingress, egress and regress thereto, during said three (3) year period. Any existing ground slips will be documented prior to the start of the construction and are specifically excluded from this provision.


IN WITNESS WHEREOF, the Parties have executed this Agreement as of the date first set forth above

**EQT PRODUCTION COMPANY**

\_\_\_\_\_  
Name: Robert Hawkins  
Title: Authorized Agent

**OWNER**

  
\_\_\_\_\_  
John R. Hildreth

  
\_\_\_\_\_  
Louise M. Hildreth



March 25, 2026

Dear Customer,

The following is the proof-of-delivery for tracking number: 889880936089

---

**Delivery Information:**

---

<b>Status:</b>	Delivered	<b>Delivered To:</b>	Residence
<b>Signed for by:</b>	Signature not required	<b>Delivery Location:</b>	541 Patterson Creek Road
<b>Service type:</b>	FedEx Priority Overnight		
<b>Special Handling:</b>	Deliver Weekday; Residential Delivery		SYCAMORE, PA, 15364
		<b>Delivery date:</b>	Mar 24, 2026 16:08

---

**Shipping Information:**

---

<b>Tracking number:</b>	889880936089	<b>Ship Date:</b>	Mar 23, 2026
		<b>Weight:</b>	0.5 LB/0.23 KG

**Recipient:**  
John R. & Loise M. Hildreth,  
541 Patterson Creek Road  
SYCAMORE, PA, US, 15364

**Shipper:**  
Olivia Pishioneri, EQT  
2200 Energy Drive  
Canonsburg, PA, US, 15317

<b>Purchase Order</b>	S001035.G1 8151.8040
<b>Department Number</b>	OPishioneri

Proof-of-delivery details appear below; however, no signature is available for this FedEx Express shipment because a signature was not required.

Thank you for choosing FedEx



March 23, 2026

Pennsylvania Department of Environmental Protection  
Office Of Oil and Gas Management  
400 Waterfront Drive  
Pittsburgh, PA 15222

RE: Application for an Order to Replug a Non-Producing Gas Well  
7371 Well  
Permit Number TBD  
Morris Township, Greene County, Pennsylvania

Dear PADEP Recipient,

Equitrans, LP, the oil and gas lessee of the well referenced above, does not object to the replugging of this well. Additionally, Equitrans, LP waives the 30-day objection period associated with this application.

If you have any other questions or concerns regarding this letter, please feel free to contact me via one of the methods below.

Best regards,

A handwritten signature in black ink that reads 'Megan Stahl'.

Megan Stahl  
Land Officer  
[megan.stahl@egt.com](mailto:megan.stahl@egt.com)  
412-660-6847



March 25, 2026

*Via E-Mail*

Pennsylvania Department of Environmental Protection  
Bureau of Oil & Gas Management  
400 Waterfront Drive  
Pittsburgh, PA 15222

RE: Application for an Order to Replug a Non-Producing Gas Well  
7371 Well  
Permit Number TBD  
Morris Township, Greene County, Pennsylvania

Dear DEP Recipient,

Please find attached the following documentation:

- Completed Form 8000-PM-OOGM0008 "Application for an Order to Clean Out and Plug or Replug a Non-Producing Gas Well"
- Well Location Plat
- Proposed plugging method
- Copy of the agreement granting EQT the right to enter the property
- Proof of notification of the surface owner and oil and gas lessors
- Statement of non-objection from Equitrans, LP the oil and gas lessee

Please note that both EQT Production Company and Equitrans, LP are both subsidiaries of EQT Corporation.

If you have any questions or concerns regarding this application, please feel free to contact me using one of the methods below.

Best Regards,

A handwritten signature in blue ink, appearing to read 'J. Zavatchan'.

John Zavatchan  
Regional Manager - Permitting  
[jzavatchan@eqt.com](mailto:jzavatchan@eqt.com)  
412-584-3132